



GENERAL NOTES

J TRACK IS FASTENED TO STUD WITH TWO SCREWS PER STUD END.

AT INTERSECTION OF HORIZ. AND VERT. WALL SECTIONS FASTENERS MUST BE APPLIED THROUGH J TRACK AND INTO I-STUDS.

MAXIMUM HORIZ. SPANS ARE DEPENDENT ON I-STUD SIZE AND GAUGE.

TEST REF.
WHI 694.0300.1

SCALE: 3"=1'-0"	TWO HOUR HORIZONTAL DUCT PROTECTION	
DATE: 2001	NATIONAL GYPSUM COMPANY	<small>DETAIL</small> 09260_09